BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to : **Original / Duplicate**

NAME OF WORK: Development of Parks in ward no.8 Kodigehalli.

Sl. No.	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
1	1050.00	Lead for disposal of debris shall be payable at carrage rates by mechanical means including loading and unloading From 13.30 Kms	cum	114.08	
2	4292.60	Clearing and grubbing road land including uprooting rank vegetation, grass, brush, shrubs, saplings and trees girth upto 300mm, by manual means, in area of thorney jungle, removal os stumps, disposal of unserviceable materials, stacking of serviceable materials labour charges complete as per specifications.	sqm	9.72	
3	59.58	Earthwork in surface excavation in ordinary soil for levelling and lowering the ground manually (other than foundation of buildings, culverts, road drains and trenches of pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m, excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of clods and neatly dressed as per specifications.	cum	83.16	
4	10.17	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement 220kgs,with 40mm and down size graded granite metal coarse aggregates @ 0.892cum and fine aggregates @o.465 cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation including cost all materials, labour, HOM of machinery, curing complete as per specifications	cum	5236.92	
5	24.41	Providing and constructing granite/trap/basalt size stone masonry in basement with cement mortar 1: 6 stone chistel dressed in courses not less than 15 cms high bond stones at two m apart in each course including cost of materials, labour, curing complete as per specifications	cum	4905.36	

No corrections - Nil

19/01

E.E. (BTP. DIV)

12/01

	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
6	1.18	Providing and laying in position plain cement concret of mix 1:2:4 with cement @ 240kgs with 20mm and down size graded granite metal coarse agregates @ 0.69cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exeeding 15 cm thick well compacted in foundation and plinth and cills, including cost all materilas, labour, HOM of machinery, curing complete as per specifications	cum	5490.72	
7	18.79	Providing and laying in position plain cement concrete of mix M20 with OPC cement @ 300kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @o.43 cum with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed -2008, machine mixed concrete laid in layers not exceeding 15cms thick well compacted in foundation, plinth and cills including cost of all materials, labour, HOM of machinery, curing complete as per specifications	cum	5991.84	
8	266.80	Supply and fixing M.S. Rectangular poles made out of 2 equal angles of 65x65x6mm welded together and fixed in cc(1:2:4) WITH 2 NOS 16mm dia M.S. hold fast rods each of length 25cms including cost of all materials cutting, bending scaffolding wherever necessary, nicely finishig the welded joints with all lead lifts and as per the directions of the Engineer-in-charge of the work and including providing 2 coats of approved quality paint over on coat of shop painting (excluding cost of earth work and concrete)	mtr	991.44	
9	174.00	Providing and fixing M.S. block pipe opf 38mm dia, of heavy guage of 14 including removing the bends, cutting the pipe and fixing pipe in between the two verticle poles (M.S. rectangular poles) and spot welding the chain link with M.S. block pipe including cost of all materials wastage in cutting and scaffolding wherever necessary with all lead and lift as directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint (P-255, I-No. 37.4)	mtr	338.04	
10	232.00	Providing chain link fencing 50mm size of 8 guage properly streched between rectangual poles and fixed with suitable bolts & nuts the free ends shall be welded to the pole and block pipe at top and bottom as required including cost of all materials, labour, lead and lifts and as per the directions of the Engineer-in-charge of work including two coats of approved quality paint over one coat of shop paint	sqm	697.68	

No corrections - Nil

E.E. (BTP. DIV) 12/01

12/01

	Approved Quantity	Description	Unit	Rates	
				In Figures	In Words
11	56.00	Providing and fixing M.S Gates as per chief Architect drawing, using 50mm*50mm 14 guage M.S hollow pipe frame work bent to ornamental shape as shown in the drawing and 35mm*6mm and 16mm*16mm squre rods for verticals alternatievly spaced at 4cms c/c in two halves and 40mm*6mm M.S flats for horizontal member and at the top cast iron spikes are provided at alternate vertical members as shown in the drawing etc.,	sqm	3299.40	
12	8585.20	Providing and applying enamel metal paint one coat (excluding priming coat) on previously painted steel or other metal surface brushing to give an even shade after cleaning oil, grease, dirt and other foreign matter, including cost of materials, labour, complete as per specifications	sqm	52.92	

No formations - Nil.

Executive Engineer 12/01/
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

"DTS Approved"

12.01.17